FINISH SCHEDULE

ROOM NO.	ROOM DESCRIPTION	FLOOR CVR'G	BASE	WALL CVR'G	CEILING	CEILING HT.	NOTES
20	BALCONY / HALL	CRPT	4"	PNT SW1130	*	9'	* SEE CEIL
21	BATH / STOR.	VCT	4"	PNT SW1130	YES	9'	
22	OFFICE	CRPT	4"	PNT SW1130	YES	9'	
23	OFFICE	CRPT	4'	PNT SW1130	YES	9'	
24	OFFICE	CRPT	4"	PNT SW1130	YES	9'	
25	OFFICE	CRPT	4"	PNT SW1130	YES	9'	
26	OFFICE	CRPT	4"	PNT SW1130	YES	9'	
27	OFFICE	CRPT	4"	PNT SW1130	YES	9'	
28	OFFICE	CRPT	4"	PNT SW1130	YES	9'	
29	OFFICE	CRPT	4"	PNT SW1130	YES	9'	
30	OFFICE	CRPT	4"	PNT SW1130	YES	9'	
31	OFFICE	CRPT	4"	PNT SW1130	NO		
32	WOMEN'S	VCT	4"	PNT SW1130	YES	9'	
33	MEN'S	VCT	4"	PNT SW1130	YES	9'	
34	OFFICE	CRPT	4"	PNT SW1130	YES	9'	
35	OFFICE	CRPT	4"	PNT SW1130	YES	9'	
36	OFFICE	CRPT	4"	PNT SW1130	NO	9'	
37	OFFICE	CRPT	4"	PNT SW1130	YES	9'	
38	OPEN	NONE			NO		
39	OPEN	NONE			NO		
40	MECHANICAL	NONE			NO		

CPRT - CARPET - QUEEN'S COMMERCIAL CARPET - SAPHIRE #650

VCT - ARMSTRONG SHELTER WHITE # 51836

BASE - AZROCK # CB-93 OR ARMSTRONG EQUAL

PNT - PAINT - SHERWIN WILLIAMS COLOR, ALL WALLS LATEX

CEILING - ARMSTRONG CORTEGA 2' x 2'

TYPICAL WRAP COLS IN BREAKMETAL TO MATCH STOREFRONT

1 SECOND FLOOR PLAN

1/8" = 1'-0"